



QUALITY CONTROL SUB DISTRICT LABORATORY,
KERALA WATER AUTHORITY,
JICA WTP MEENAD, THOLICODE. P.O, PUNALUR, KOLLAM - 691333.

TC-10536

ULR - TC105362300001479F

Test Report					
Report No - 2023/QCSDL/JICA/1590		Issue Date : 12.07.2023			
Customer Name & Address		1. Date of Receipt : 07.07.2023			
HOLY CROSS PUBLIC SCHOOL, PANDITHITTA, THALAVOOR, PH. 8281162715.		2. Sampling done by - CUSTOMER			
		3. Sample Code : 2023/QCSDL/JICA/1590			
		4. Source of Sample : Open Well Water			
		5. Sample Quantity : 2 Litres			
		6. Test Performing Dates			
		From : 07.07.2023 To : 11.07.2023			
	Characteristics	Unit as per IS 10500	Test Method	Maximum Acceptable limits as per IS 10500 - 2012	Result
1	Turbidity	(NTU)	IS 3025 (Part 10) : 1984 (Nephelometric Method)	1	1.74
2	pH at 25 °C		IS 3025 (Part 11) : 2022 Electrometric Method	6.5 to 8.5	5.936
3	Total Hardness (as Ca CO ₃)	(mg/L)	IS 3025 (Part 21) : 2009 EDTA Method	200	18
4	Chloride (as Cl)	(mg/L)	IS 3025 (Part 32) : 1988 Argentometric Method	250	7.92

NB:- 1.The results stated above related only to the sample(s) submitted for testing. 2.This test certificate shall not be reproduced except in full without the written approval of the Laboratory. 3. The results apply to the sample as received. 4. Samples will be retained only for 7 days after reporting the test results to the customer

Verified By
Name : Aswathy K Raj
Sanitary Chemist

Aswathy

Authorized By
Name: Jinu George
Sanitary Chemist

Jinu George
12-07-23

KWA/QCSDL/JICA/19

Issue No. 01

* End of Report *
Issue Date : 06.12.2021
Page 1 of 1

Rev. No. 02

Rev. Date : 17.05.2023

SANITARY CHEMIST
QUALITY CONTROL SUB DISTRICT LAB
JICA WTP MEENAD
KERALA WATER AUTHORITY
PUNALUR



QUALITY CONTROL SUB DISTRICT LABORATORY,
KERALA WATER AUTHORITY,
JICA WTP MEENAD, THOLICODE. P.O, PUNALUR, KOLLAM - 691333.

Test Report					
Report No - 2023/QCSDL/JICA/1590				Issue Date : 12.07.2023	
Customer Name & Address		1. Date of Receipt : 07.07.2023			
HOLY CROSS PUBLIC SCHOOL, PANDITHITTA, THALAVOOR, PH. 8281162715.		2. Sampling done by - CUSTOMER			
		3. Sample Code : 2023/QCSDL/JICA/1590			
		4. Source of Sample : Open Well Water			
		5. Sample Quantity : 2 Litres			
		6. Test Performing Dates From : 07.07.2023 To : 11.07.2023			
	Characteristics	Unit as per IS 10500	Test Method	Maximum Acceptable limits as per IS 10500 - 2012	Result
1	Electrical Conductivity (at 25° C)	micro mhos/cm	IS 3025 (part 14) - 1984		31.18
2	Iron (as Fe)	(mg/L)	IS 3025 (Part 53) - 2003 1,10 Phenanthroline Method	1	0.13
3	Nitrate (as NO ₃)	(mg/L)	APHA 23rd Edition 4500 -NO ₃ B: 2017 UV Spectrophotometric Screening Method.	45	1.17

NB:- 1. The results stated above related only to the sample(s) submitted for testing. 2. This test certificate shall not be reproduced except in full without the written approval of the Laboratory. 3. The results apply to the sample as received. 4. Samples will be retained only for 7 days after reporting the test results to the customer

Verified By

Name : Aswathy K Raj
Sanitary Chemist

Aswathy

Authorized By

Name: Jinu George
Sanitary Chemist

Jinu George

KWA/QCSDL/JICA/19

Issue No. 01

* End of Report *

Issue Date : 06.12.2021

Rev. No. 01

Rev. Date : 06.05.2022

Page 1 of 1

SANITARY CHEMIST
QUALITY CONTROL SUB DISTRICT LAB
JICA WTP MEENAD
KERALA WATER AUTHORITY
PUNALUR



QUALITY CONTROL DISTRICT LABORATORY
KERALA WATER AUTHORITY
CANTONMENT P O, KOLLAM - 691 001

REPORT ON ANALYSIS OF WATER

Report No - 2023/QCSDL/JICA/1590			Date: 13/07/2023	
Customer Name & Address			1. Date of Sample received: 07/07/2023	
HOLY CROSS PUBLIC SCHOOL, PANDITHITTA, THALAVOOR 8281162715			2. Sampling done by: Health Inspector, Primary Health Centre, Thalavoor	
			3. Sample Quantity : 250 ml	
			4. Source of Sample : Well Water	
			5. Sample Code : 2023/QCSDL/JICA/1590	
			6. Test Performing Dates From : 07/07/2023 To : 11/07/2023	
Sl. No.	Parameters	Acceptable limits as per IS 10500 - 2012	Test Method	Result
1	Total Coliforms/ 100 ml	Shall not be detected/100 ml	IS 15185 : 2016 ISO 9308 - 1 : 2014	ABSENT
2	E. coli /100 ml	Shall not be detected/100 ml	IS 15185 : 2016 ISO 9308 - 1 : 2014	ABSENT

NB:- The results stated above related only to the sample(s) submitted for testing. This test certificate shall not be reproduced except in full without the written approval of the Laboratory.

Authorized By

*** End of Report ***

KWA/KLM/R/19 Issue No. 01 Issue Date: 22.10.2020 Rev.No: 01 Rev. Date: 15.03.2021
Page 1 of 1

Biologist,
Quality Control District Laboratory
Kerala Water Authority
Kollam.



കേരള സംസ്ഥാന ആരോഗ്യവകുപ്പ്
തലവൂർ ഗ്രാമപഞ്ചായത്ത്
പ്രാഥമികാരോഗ്യ കേന്ദ്രം, തലവൂർ



സാനിറ്ററി സർട്ടിഫിക്കറ്റ്

(CERTIFICATE OF SANITARY FITNESS)

നമ്പർ 20/23-24.

കൊല്ലം ജില്ലയിൽ തലവൂർ ഗ്രാമപഞ്ചായത്തിൽ Bramble നിയർ
പ്രദേശത്ത് 1.ാം വാർഡിൽ കെട്ടിടനമ്പർ 457ൽ ചെറുവിലാസം
ഹോളിക്രോസ്സ് പബ്ലിക് സ്കൂൾ, ചെറുവിലാസം
എന്നയാളുടെ ഉടമസ്ഥതയിലുള്ള കെട്ടിടത്തിൽ ചെറുവിലാസം
ഹോളിക്രോസ്സ് പബ്ലിക് സ്കൂൾ, ചെറുവിലാസം, ബ്രാമ്ല നിയർ
നടത്തിവരുന്ന ഹോളിക്രോസ്സ് പബ്ലിക് സ്കൂൾ

.....എന്ന
വിദ്യാർത്ഥി
ജന്മപരസ്ഥാപനത്തിൽ 8.8.23ൽ നടത്തിയ പരിശോധനയിൽ
സാനിറ്ററി വ്യവസ്ഥകൾ തൃപ്തികരമായി പാലിച്ചിട്ടുള്ളതായി സാക്ഷ്യപ്പെടുത്തുന്നു.
ആയതിനാൽ ടിയാൻ മേൽ സ്ഥാപനം പ്രവർത്തിപ്പിക്കുന്നതിന് 2023-24
വർഷത്തേക്കുള്ള സാനിറ്ററി സർട്ടിഫിക്കറ്റ് അനുവദിക്കുന്നു.

പൊതുജനാരോഗ്യ നിയമങ്ങളും നിലവിലുള്ള മറ്റ് നിയമങ്ങളും അപേക്ഷകൻ
സ്വയം സാക്ഷ്യപ്പെടുത്തി നൽകിയിരിക്കുന്ന സത്യവാങ്മൂലവും നിബന്ധനകളും
പാലിക്കാതിരുന്നാൽ ഈ സാക്ഷ്യപത്രം റദ്ദാക്കുന്നതും മറ്റ് നടപടികൾ
സ്വീകരിക്കുന്നതുമാണ്.

തലവൂർ

തീയതി: 10.8.23



പൊൽത്ത് ഇൻസ്പെക്ടർ

പ്രാഥമികാരോഗ്യ കേന്ദ്രം
HEALTH INSPECTOR
Primary Health Centre
Thalavoor